KOLAR DIVISION.

Dated 9th August 1905.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Kolar Division, up to 9th September 1905 for constructing Medical Officer's Quarters at Kolar Gold Fields. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of March 1906.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Kolar between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed. The rates tendered should include Royalty on stones, &c., removed from Government lands, to be paid to the Government.

4. Each tender must be accompanied by a deposit of Rs. 100 in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Medical Officer's Quarters at Kolar Gold Fields"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

ABSTRACT.

Details of work.	*Per*	*Quantity.*	*Remarks.*
Earthwork excavation and filling basement ...	C. yd.	127	
Stone in chunam, foundation and basement ...	C. ft.	4,520	
Burnt brick in chunam, superstructure ...	,,	4,859	
Arch work, burnt brick in chunam	,,	96	
Plastering with chunam	Sqr.	85·73	
White and colour washing	,,	85·73	
Flooring with Mangalore tiles over 3" concrete and cement pointing	,,	6·85	Rate only for fixing tiles to be given.
Flooring with Cudappa slabs over 3" concrete and cement pointing	,,	3·91	
Mangalore tile roofing with ridge tiles, &c., complete ...	,,	29·38	do
Mangalore ceiling tiles	,,	7·27	
Eave board	R. ft.	65	
Pointing with chunam	Sqr.	4·30	
Teakwood work including wood oiling	C. ft.	194·23	
Do pillars with base and capital complete ...	Each	6	
Concrete 9" × 9"	R. ft.	222	
Burnt stone slabs roughly dressed	S. ft.	685	
Teakwood doors pannelled	,,	274	
Teakwood windows pannelled with iron bars complete with glazed shutters	,,	132	
Do ventilators	,,	25	
Zinc sheets under valley	R. ft.	68	
Chocolate painting to doors and windows, &c. ...	Sqr.	13·40	
Teakwood planking 1½" thicks at ends of front verandah.	,,	36	
Coping with brick in chunam and plaster over ...	R. ft.	34	
Gravel flooring	C. yds.	20	
Teakwood doors battened	S. ft.	95	
Do windows do	,,	110	
Do ventilators do	,,	26	
Honey-comb tiled work	Sqr.	24	
Plain cornice	R. ft.	227	
Constructing cisterns in bath and kitchen	Lump sum.		
Clearing site, etc.	,,		
Teakwood gate complete big	,,		
Wicket gate	,,		
Constructing latrine similar to what is attached to the Hospital close by	,,		
Opening out roads, etc.	,,		
Constructing drains, etc.	,,		
Water-supply	,,		

B. SUBBA RAO, *Executive Engineer.*